MODEL

- ❑ **MV-HEP** - MULTI-VENT DUAL CHAMBER LAMINAR FLOW PANEL WITH HEPA FILTER

INSTALLATION

- ❑ LAY-IN T-BAR GRID SYSTEM
- ❑ SURFACE / HARD CEILING (SPECIFY BATTEN ARRANGEMENT PAGE A-33)

NOMINAL WIDTH

- ❑ 12"
- ❑ 36"
- ❑ 24"

NOMINAL LENGTH

- ❑ 2'
- ❑ 5'
- ❑ 3'
- ❑ 6'
- ❑ 4'

INLET SIZE & LOCATION

TOP INLET

- ❑ 4" - 8" Ø (12" WIDE UNITS)
- ❑ 4" - 16" Ø (24 & 36" WIDE UNITS)

END INLET

- ❑ 8" Ø MAXIMUM

SIDE INLET

- ❑ CONTACT FACTORY FOR SIZES

MATERIAL AND FINISH

DISTRIBUTION PANEL

- ❑ STEEL WITH WHITE BAKED EPOXY
- ❑ ALUMINUM WITH WHITE BAKED EPOXY
- ❑ 304 STAINLESS STEEL, #4 POLISH
- ❑ 304 STAINLESS STEEL WITH WHITE BAKED EPOXY

DUAL CHAMBER PLENUM

- ❑ STEEL WITH WHITE BAKED EPOXY
- ❑ ALUMINUM WITH WHITE BAKED EPOXY
- ❑ 304 STAINLESS STEEL, 2B MILL FINISH
- ❑ 304 STAINLESS STEEL WITH WHITE BAKED EPOXY

FOR ALUMINUM ANODIZED FINISHES, CONTACT FACTORY.

ACCESSORIES

- ❑ LIGHT-ALERT FILTER MONITORING SYSTEM
- ❑ 1/2" FOIL FACED EXTERNAL INSULATION